



NOTES: TYPE IV DOW RIGID EXTRUDED INSULATION MUST BE 60 PSI (414 kPa) (COMPRESSIVE STRENGTH) BOARD MINIMUM.

THE PEDESTAL SHOWN IS 1/2 A TYPICAL UNIT, WITH THE TRANSVERSE SPACER LUGS LEFT INTACT TO MAINTAIN THE APPROPRIATE JOINT SPACE AT TERMINATION.

MINOR LEVEL ADJUSTMENTS CAN BE MADE BY PLACING SHIMS UNDERNEATH THE PEDESTAL. SHIMS PLACED ON TOP OF THE PEDESTAL MUST NOT EXCEED THE HEIGHT OF THE SPACER LUGS.

REFER TO APPLICABLE MM6125-FR ROOFING OR WATERPROOFING GUIDELINE DETAILS FOR PROPER MEMBRANE/FLASHING DETAILS AND ALTERNATIVES.



PLAZA DECK  
ASSEMBLY  
ARCHITECTURAL PAVER

TYPICAL TERMINATION  
AT WALL/PARAPET/CURB

HYDROTECH MEMBRANE CORP.

NO SCALE

UAC-1